PRIMETEST 250

A comprehensive handheld PAT tester. The Engineer's ideal companion.



Seaward's lightweight, portable Primetest 250 PAT tester is unique in its range of safety tests. The PrimeTest 250 will perform all of the tests required by the IEE Code of Practice, including RCD trip, protective conductor current and touch current where required. The unit also includes a 250V DC insulation test suitable for testing sensitive electrical appliances and surge protected leads.

The PrimeTest 250 is ideal for ensuring that all workplace electrical equipment does not pose a danger to users -including three-phase machinery. As a result, 3-phase industrial plant and equipment used in factories, workshops, schools and colleges can all be tested safely and effectively.

The unique range of tests incorporated in this lightweight and highly versatile instrument means that most workplace appliances can be tested using long life battery power. However, when protective conductor current or touch current measurements are required, simply connecting a mains supply will automatically select the correct test sequence.

The Primetest 250 is designed for ease of use and carries out all electrical safety tests against pre-set limits with measured test results and clear PASS/FAIL indication on a large display.

The PrimeTest 250 is an easy-to-use tester which is ideal for those who need to test a wide range of electrical equipment.

*For 3 phase and RCD testing, accessories are required.



Web: www.seaward.co.uk Email: sales@seaward.co.uk

Key Features

- Easy to use manual PAT tester
- Comprehensive range of tests
- Clear PASS/FAIL indication
- Capable of both equivalent leakage (using battery power) and protective conductor / touch current (using mains power)
- Lightweight
- Automatic test sequences

Ideal Users

- In-house safety testing engineers
- Electrical Contractors
- Service & Maintenance Engineers

Seaward

Bracken Hill, South West Industrial Estate, Peterlee, SR8 2SW **Tel:** +44 (0) 191 5863511 **Fax:** +44 (0) 191 5860227

PRIMETEST 250 SPECIFICATIONS

SPECIFICATIONS

Earth continuity

Output Current: Test Voltage (o/c): Test Duration (Class I Test): Display Range: Pass Value (Class I Test): 200mA minimum into 2Ω 9V DC nominal 2s nominal 0.01 ohm to 19.99 ohm 0.2 Ω

Insulation resistance

Test Voltage: Test Duration (Class I or II): Display Range: Pass Value: 250/500VDC @1mA nominal, < 2mA (s/c) 2s 0.01 Mohm to 19.99 Mohm 1.0 M Ω Class I 2.0 M Ω Class II

Equivalent leakage

Test Voltage: Test Duration: Display Range: Pass Value: 40V Nominal AC 50Hz Open Circuit 2s – 30s nominal 0.1 mA to 19.99mA 0.75mA CLI / 0.25mA CL II

IEC lead test

Test voltage: Test Duration: Test: 5V DC nominal Time for test (2s max) Live / Neutral Checks for o/c, s/c and crossed

Protective Conductor Current

Test Voltage: Test Duration: Display Range: Pass Value: Supply Voltage, max current 13A 30s maximum 0.15 mA to 9.99 mA 0.75mA/3.5mA (user selectable with 0.75mA as default)

Touch current

Test Voltage: Test Duration: Display Range: Pass Value: Supply Voltage, max current 13A 30s maximum 0.10 mA to 5.00 mA 0.25mA

3 phase differential leakage current *Requires 3 phase adaptor accessory

Test Voltage: Test Duration: Display Range: Pass Value: 3 phase supply voltage Continuous measurement 0.10 mA to 9.99 mA 3.5mA

RCD trip time

Test Voltage: Test Current: Test Current Phase: Measuring Range: Pass Value:

Mains supply voltage 10mA / 30mA rms sinusoidal 0°/180° auto switched on alternate tests 0ms – 500ms 200ms

Power socket check

Input voltage range: Indicates configuration of voltage potential:- 225 - 254V AC max current 13A UK

Line potential phase to earth Line potential phase to neutral Line potential neutral to earth



WORLD LEADERS IN SAFETY TEST AND MEASUREMENT

Seaward test and measurement companies include:



